

OREGON CORNER RESTORATION FORM

Section 32 Township 4 N Range 29 E

V-9

County UMATILLA Date 3/95

CORNER DESIGNATION

NE Cor.

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. ORIG SUR. DAVENPORT 1861 # 101

He set a post in mound with charred stake

1903 Krumbein Set BC. Co# 83-79-B

Monument(s) & Accessories Found: (Condition and Source)

Nothing

Monument Detail

Sketch



Monument Set (Procedures and Description)

By retracing Fraley's 1950 survey (the E line sec. 32)

I set 5/8" x 3/8" rebar with 2" Alum Cap stamped as above

SEE MY 1994-1 COUNTY PUBLIC MONUMENTATION SUR.

New Accessories

Alum tag <sup>#951</sup> in RR Tie F. Post	Bears	N 29° 20' 14" E	81.71 Ft.
" " " " " "	"	S 53° 42' 05" E	66.88 Ft.
" " " 9" Locust F. Post	"	S 29° 03' 21" W	28.40 Ft.
1" x 3/8" I Pipe with 2 3/8" BC.	"	N 89° 09' 20" E	36.50 FT.

Location & Comments

From Intersection

Harding Ave with

Edwards Rd. Go

N on Edwards 1/2

Mile to Cor.

Compass Declination \_\_\_\_\_

Firm/Agency EDWARDS

SURVEYING

Address P. Box 763

HERMISTON, OR 97838

Party Chief D. EDWARDS

Notes \_\_\_\_\_

Witness J. COPPOCK

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

RENEWS 12/31/95

RECEIVED BY \_\_\_\_\_

Umatilla County Surveyor \_\_\_\_\_

Date \_\_\_\_\_

Rec'd By \_\_\_\_\_

No. 95-60-B