

GPS CONTROL STATION

OREGON STATE PLANE, NORTH ZONE

STATION NAME: 4N29X9 GEODETIC COORDINATE: NAD 83(91)

SECTION: E 1/4 S32 LAT: 45°47'3.15150" N  
T. 4N., R. 29 E., W. M. LONG: 119°12'17.95750" W  
UMATILLA COUNTY  
OREGON

STATE PLANE CO-ORDINATES,  
NAD 83-91, INT. FT. :

DATE SURVEYED: March, 1998

N: 774663.227

SURVEYOR: DAVID L. HADDOCK  
PLS 852

E: 8532467.275

THETA: 0°55'6.26"

SCALE FACTOR: 0.99995230

FIRM: HADDOCK SURVEYING  
P. O. BOX 1574  
PENDLETON, OR 97801  
(541) 276-2174

ELEV: 600


ELEV. DATUM: NGVD29

ORDER: SECOND ORDER,  
CLASS I

---

LOCATION: From the intersectin of Harding Avenue and US 395 in the City of Stanfield, go east on Harding Ave. to the intersection with South Edwards Road. The cap is in the center of the intersection approximately 6" below the surface of the pavement.

STATION: Station is a 2 1/4 inch brass disc on a galvanized iron pipe.



*David L. Haddock*



98-155-c