

OREGON CORNER RESTORATION FORM

SECTION 34 TOWNSHIP 4 NORTH RANGE 29 EAST Z-15
COUNTY : UMATILLA DATE 8-98

CORNER DESIGNATION

SOUTH 1/4

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNCOVERED
 SURVEYED IN
 REFERENCED

PREVIOUS RENEWALS / SURVEYS, ETC.


ORIGINALLY SURVEYED IN 1859 BY GATES UNDER CONTRACT #84. HE SET A POST IN A MOUND OF DIRT.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

NOTHING

MONUMENT DETAIL

SKETCH



MONUMENT SET (PROCEDURES AND DESCRIPTION)

BY SINGLE PROPORTION I SET A 1" X 30" IRON PIPE WITH A 2 3/8" BRASS CAP STAMPED AS ABOVE, 4" BELOW THE SURFACE OF A GRAVELED ROAD.

NEW ACCESSORIES FROM WHICH

AN ALUMINUM TAG #951 ON A POWER POLE LIES N 62°.57'00" W, 58.35 FEET.
AN ALUMINUM TAG #951 ON A POWER POLE LIES N 7°.43'30" E, 108.42 FEET.
AN ALUMINUM TAG #951 ON A POWER POLE LIES N 63°.18'00" E, 83.55 FEET.
AN ALUMINUM TAG #951 IN A RXR TIE GATE POST LIES S 14°.03'20" E, 14.41 FEET.

LOCATION AND COMMENTS

AT THE INTERSECTION OF OLD STAGE ROAD AND COOPER ROAD.

COMPASS DEC.

FIRM/AGENCY
EDWARDS SURVEYING
P.O. BOX 763
HERMISTON, OREGON 97838
97838

PARTY CHIEF
D. EDWARDS

NOTES

WITNESS
CURTIS J FAVOREL

SURVEYOR'S SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/99

RECEIVED BY

Umatilla County Surveyor

Date 10-98

Rec'd By JK

No. 98-213-C