

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 02/27/07

CORNER DESIGNATION: 4N30, G-19, The Center One-Quarter of Section 11.

PREVIOUS RENEWALS/SURVEYS ETC.: None.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL: See Below.

MONUMENT SET:

At the calculated position for the center quarter of section 11, determined by intersecting lines between opposite one-quarter corner positions, set a 5/8"x30" iron rebar with a 1 1/4" red plastic cap stamped "OR PLS 1106 WA PLS 17372", with cap flush with the ground.

New Accessories:

- A Silver Deep-1 magnet buried 20" below ground level bears North 40° East, 29.5 feet.
- A Blue Deep-1 magnet buried 20" below ground level bears South 65° East, 25.6 feet.
- A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372", in North-South fence line bears South 37 1/2° West, 20.2 feet.
- A 5/8"x24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372", in North-South fence line bears North 21 1/2° West, 37.1 feet.

Attached bearing object signs to iron rebar and buried bearing object signs with magnets. Set steel fence post with witness sign attached 1 foot West of monument.

LOCATION AND COMMENTS: Corner is located approx. 12 feet East of a fence running North-South and South 15° East - 58.0 feet from a fence corner post with fences South and East. A 5/8" iron rebar used for survey control bears North 18°51' East - 27.60 feet.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Micah Engum

/4N30G19

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08