

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/16/05

CORNER DESIGNATION: 4N30G21, the East 1/4 Corner of Section 11.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner was originally established by Dolphus S. Payne under contract No. 100, dated August 1, 1861. Original notes state: Set charred stake, with mound, trench and pits as per instructions, for 1/4 Section Cor.

MONUMENT AND ACCESSORIES FOUND:

Found and accepted a fence corner with fences running East, West and South as best remaining evidence of original corner location.

MONUMENT MARKING DETAIL:

T4N R30E
1/4
S11|S12
2005
PLS 1106

MONUMENT SET:

At a point 6" North of fence corner post, set a 2 1/2" brass cap on 1 1/4" by 30" galvanized iron pipe, 30" in the ground. Monument marked as shown in Monument Marking Detail.

New Accessories:

A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", with cap set 2" above ground in fence line bears: South 85° East a distance of 22.9 feet.
A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", with cap set 2" above ground in fence line bears: South 01° West a distance of 16.6 feet.
A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", with caps set 2" above ground in fence line bears: South 01° West a distance of 44.3 feet.
A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", with cap set 2" above ground in fence line bears: North 89° West a distance of 43.8 feet.

Attached "witness" sign to fence corner post 6" South of monument. Wired bearing object signs to rebar accessories.

LOCATION AND COMMENTS:

Located at fence intersection, just East of a North-South field access road.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

4N30G21

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-06