

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 05/23/05

CORNER DESIGNATION: 4N31E01. Section corner common to Sections 6 & 7 only.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by David P. Thompson, under Contract No. 81, dated July 8, 1859. Record states: Set post for cor. to Secs. 6, 7 1 & 12, and built mound of earth with pits, trench, etc., as per instructions.

Corner was recovered by Dolphus Payne, under Contract No. 100, dated August 1st, 1861. Record states: Intersect Tp. Line, 6.28 chs N. of post Cor. to Secs. 1 & 12 R.30 and 6 & 7, R 31, this being out of limits, we measured the line bet. Secs. 12 & 7 (Guide Meridian) and found to be N. 79.10 chs. in length, which makes our intersection with the Tp. line, (counting the 5.00 chs. lacking bet. Secs. 24 & 19), just 38 lks. N. of our proper closing point, therefore at 5.90 chs. N. of post on Guide Meridian set charred stake, with mound, trench and pits for Cor. to Secs. 1 & 12, T4N., R30E.

MONUMENT AND ACCESSORIES FOUND: Found fence corner with fences extending East and N 80° W.

**MONUMENT MARKING DETAIL:**

T4N  
R30E R31E  
| S6  
| S7  
2005  
PLS 2005

MONUMENT SET: I accepted the old fence corner with fences East and N 80° W as best remaining evidence of the original corner position. Set 2 1/2" brass cap on a 2 1/2" x 30" galvanized iron pipe, 28" in the ground, just South of fence corner, marked as shown in Monument Marking Detail.

**New accessories:**

- A 5/8" x 30" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears East, 25.8 feet.
- A 5/8" x 30" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears East, 52.8 feet.
- A 5/8" x 30" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 80° West, 46.5 feet.
- A 5/8" x 30" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 80° West, 22.7 feet.

All rebar accessories are set in fence lines and have bearing object signs attached. Nailed "witness" sign to wood fence corner post, North of corner monument.

LOCATION AND COMMENTS: Corner falls in unfarmed scab area, East of old road running North.

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, LSIT

4N31E01

RECEIVED BY  
Umatilla County Surveyor  
Date 6-05  
Rec'd By KK  
No. 15-122-R

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*William R. Wells*  
OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106  
*renews 6-30-06*