

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 02/13/07

CORNER DESIGNATION: 4N31, J-7, The North One-Quarter Corner of Section 17.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by W.H. Odell, under GLO Contract No. 114, dated July 2, 1866. Notes state: Set post corner for 1/4 section, on land that slopes to the N.W., drove charred stake, dug pits, and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner point falls at intersection of old field berms extending North and West.

MONUMENT MARKING DETAIL:

T4N R31E
1 S8
4 S17
2007
PLS 1106

MONUMENT SET:

Held intersection of field berms extending West and North as best remaining evidence of the original corner location. At intersection of berms, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap 2 inches above ground level, marked as shown in Monument Marking Detail.

New Accessories:

A silver deep-1 magnet buried 20" in the ground bears North 64° East, 31.5 feet.
A blue deep-1 magnet buried 20" in the ground bears South 31° East, 28.0 feet.
A purple deep-1 magnet, buried 20" in the ground bears South 87 1/2° West, 23.7 feet.
A orange deep-1 magnet, buried 20" in the ground bears North 24° West, 34.1 feet.
Buried bearing object sign with each deep-1 magnet accessory. Set steel fence posts 1.5' West of monument and 2.5' South of monument with witness signs attached.

LOCATION AND COMMENTS:

Corner is located near hilltop on Northwest slope.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Micah Engum

/4N31J7



07-30-B