

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/23/05

CORNER DESIGNATION: 4N31L-01, The West Quarter Corner of Section 18 only.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by David P. Thompson, under Contract No. 81, dated July 8, 1859. Record states: Set post for 1/4 Sec. Cor. and built mound of earth with pits, trench, etc., as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N
R30E R31E
| 1 S18
| 4
2005
PLS 1106

MONUMENT SET: Corner was re-established mid-way and on line between the Southwest and Northwest corners of Section 18. See Record of Survey filed concurrently. At the re-established corner position, set a 2 1/2" brass cap on 2 1/2" by 30" galvanized iron pipe, with cap 20" below ground line in wheat field. Cap marked as shown in Monument Marking Detail.

New accessories:

A 5/8" x 30" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 17° West, 35.4 feet.

A 5/8" x 30" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears West, 8.3 feet. Set steel fence post by this rebar accessory and attached "witness" sign.

A 5/8" x 30" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 11° West, 38.6 feet.

A 3/4" brass washer stamped "PLS 1106", nailed 1 foot above ground line in Umatilla Electric power pole bears North 03° West, 121.7 feet.

Attached bearing object signs to all accessories. Rebar accessories are in a North-South fence line on the East side of Terney Road.

LOCATION AND COMMENTS:

Corner falls in wheat field, 8 feet East of North-South fence line on East side of Terney Road. Corner falls 22 feet East of centerline of road.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

4N31L01

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-06

RECEIVED BY
Umatilla County Surveyor
Date 6-05
Rec'd By KK
No. 05-123-B