

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/20/05

CORNER DESIGNATION: 4N31EN3, The South quarter corner of Section 18.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Wm. H. Odell, under Contract No. 114, dated July 2, 1866. Record states: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: Fence corner with fences East and North-South. 1956 photograph shows a field line extending West from the fence corner. No traces of field line exist today.

MONUMENT MARKING DETAIL:

T4N R31E
1 S18
4 S19
2005
PLS 1106

MONUMENT SET: Accepted fence corner with fences to the North-South and East as best remaining evidence of the original corner position. Set a 2 1/2" brass cap on 2 1/2" x 30" galvanized iron pipe, 28" in the ground, just west of a fence corner post, marked as shown in Monument Marking Detail.

New accessories:

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears North, 33.6 feet, (in fence).

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears East, 40.0 feet, (in fence).

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 39° East, 29.6 feet, (in scab land between fields).

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears South, 34.0 feet, (in fence).

Attached witness sign to fence corner post East of monument. Attached bearing object signs to all rebar accessories.

LOCATION AND COMMENTS: Corner located at fence corner with fences North-South and East.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

4N31N03

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-06

RECEIVED BY

Umatilla County Surveyor

Date 6-05

Rec'd By KK

No. 05-123-B