

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/24/07

CORNER DESIGNATION: 4N31, N-5, The Southwest Corner of Section 17.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was originally established by W.H. Odell, under GLO Contract No.114, dated July 2, 1866. Notes state: Set post corner for 17, 18, 19 & 20.

MONUMENT AND ACCESSORIES FOUND: Held East side of old "H" brace in line with fence extending West. The corner point was calculated on Survey No. 05-123-B, but not monumented.

MONUMENT MARKING DETAIL:

T4N R31E
S18 | S17
S19 | S20
2007
PLS 1106

MONUMENT SET:

Held point just East of old "H" brace as best remaining evidence of original corner location and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap 2 inches above ground level, marked as shown in Monument Marking Detail.

New Accessories:

A 3/4" brass washer stamped "PLS 1106", 1 foot above ground level in a railroad tie gate post bears North 73° East, 34.0 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap stamped "OR PLS 1106, WA PLS 17372", with cap 1 inch above ground level in fence, bears North 85 1/2° East, 66.7 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap stamped "OR PLS 1106, WA PLS 17372", 1 inch above ground level in fence, bears South 81° West, 18.3 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap stamped "OR PLS 1106, WA PLS 17372", 1 inch above ground level in fence, bears South 86° West, 52.0 feet.

Attached bearing object signs to all rebar accessories and beside brass washer accessory on railroad tie. Attached witness sign to H-brace post 0.5 feet West of monument.

LOCATION AND COMMENTS:

Corner is located in East-West fence line, near a gate. Can drive to corner along field road coming in from Southeast.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Micah Engum

/4N31N5

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08