

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/24/07

CORNER DESIGNATION: 4N31, N-7, The South One-Quarter Corner of Section 17.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by W.H. Odell, under GLO Contract No. 114, dated July 2, 1866. Notes state: Set post corner for 1/4 section, drove charred stake, dug pits, and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner point falls at old fence corner.

MONUMENT MARKING DETAIL:

T4N R31E
1 S17
4 S20
2007
PLS 1106

MONUMENT SET:

Held old fence corner with fences West and South as best remaining evidence of the original corner location. This fence corner was also held on Survey No. 86-33-B. At a point just East of said fence corner, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap 2 inches above ground level, marked as shown in Monument Marking Detail.

New Accessories:

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap stamped "OR PLS 1106, WA PLS 17372", in field berm, bears North 87° East, 27.8 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap stamped "OR PLS 1106, WA PLS 17372", at Southerly end of fence which formerly extended South bears South 02° West, 25.4 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap stamped "OR PLS 1106, WA PLS 17372", in fence extending West bears North 89° West, 49.8 feet.

Triangulation Station Laurila, a brass disk set in concrete, bears North 89° 58' 36" East, 192.21 feet.

Attached witness sign to fence post West of corner and attached bearing object signs to all rebar accessories.

LOCATION AND COMMENTS:

Corner is at a point about 1 foot East of fence corner post, partial fence to the south, and a good fence to the West.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Micah Engum

/4N31N7

