

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 08/21/13

CORNER DESIGNATION: 3N32, A01, The Northwest Corner of Section 6.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D. S. Payne, under Contract 100, dated August, 1, 1861. Notes state: Set charred stake with mound trench and pits as per instrs. for corner to Township 3 & 4 N. Ranges 31 & 32 East.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N  
R31E R32E  
36 | 31  
1 | 6  
2013  
T3N R32E  
PLS 54657

MONUMENT SET: Held intersection of field berms North, South and West as best remaining evidence of the corner position and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top flush with the ground. Monument stamped as shown in "Monument Marking Detail", from which:

- A silver deep-1 magnet 20" in the ground bears North 49 1/2° East, 37.7 feet.
  - A pink deep-1 magnet 20" in the ground bears South 44° East, 42.7 feet.
  - A blue deep-1 magnet 20" in the ground bears South 35° West, 37.9 feet
  - A 5/8" x 24" iron rod with 1 1/4" purple plastic cap stamped "Wells Surveying, PLS 54657" bears North 44° West, 21.4 feet.
- Buried bearing object tags with magnets. Attached bearing object to rebar. Set steel fence post 6" East with witness post sign attached.

LOCATION AND COMMENTS: Corner falls at a point with field berms North, South and West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N= 773257.82'  
E= 8617837.26'

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS  
Dean Roy

\3N32A01

