

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 10/02/18.

CORNER DESIGNATION: N-5, The Southeast corner of Section 18, Township 4 North, Range 33 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Odell and Lewis, Deputy Surveyors, under Contract No. 110, dated February 7, 1865. Notes state:

Set post corner for Secs. 17, 18, 19 & 20. Drove charred stake. Dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Reestablished corner point at the intersection of centerline of Koeboke Road (East-West) with a field berm extending South. There is a crooked field line extending North from the corner.

**MONUMENT MARKING DETAIL:**

T4N R33E  
S18 | S17  
-----  
S19 | S20  
2018  
PLS 1106

MONUMENT SET: Set a 2" aluminum cap on 5/8 by 24" rebar with aluminum cap 8" below road surface for corner. Cap marked as shown in Monument Marking Detail.

**New accessories:**

- A brass washer stamped "PLS 1106", nailed to the East side of a 24" locust tree, 2 1/2' above ground bears N 02° E, 225.0'.
- A 5/8" by 24" rebar with red plastic cap bears S 06° E, 22.4'.
- A brass washer stamped "PLS 1106", nailed to the side of locust post, 1 foot above ground line bears S 14° W, 19.6'.
- A 5/8" by 24" rebar with red plastic cap bears S 32° W, 20.4'.

Red plastic caps are marked "ORPLS 1106 W/APLS 17372". All rebar accessories have "bearing object" signs wired to them.

Nailed "Witness" sign to the locust post South of corner monument.

LOCATION AND COMMENTS: Corner is located at the intersection centerline of Koeboke Road and field berm extending South.


FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

IAN33N-5

Surveyor's Seal



*W. R. Wells*



*renews 6-30-20*

**RECEIVED BY**

Umatilla County Surveyor  
Date: 10/11/2018  
Rec'd By: TMA  
No: 18-087-R