

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/01/01

CORNER DESIGNATION: J-1, Northwest Quarter of Section 18, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. H. Odell, under Contract 114, dated July 2nd, 1866. Record states: Set post cor. for secs. 12, 13, 7 & 18; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N
S12 | S7
S13 | S18
2001
PLS 1106

MONUMENT SET: At position determined by single proportionate measure between the recovered West 1/4 Corner of Section 18 and the recovered Southwest Corner of Section 6, set a 2 1/2" aluminum cap on 2 1/2" x 30" aluminum pipe with cap buried 14" below ground level, marked as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet 18" buried in ground bears N 47° E, 29.1 feet.
- A purple deep-1 magnet 18" buried in ground bears S 48 1/2° E, 25.6 feet.
- A blue deep-1 magnet 18" buried in ground bears S 39° W, 25.8 feet.
- The center of a 6" diameter metal post bears N 55° W, 15.4 feet.
- Buried bearing object signs with deep-1 magnets. Attached "witness" sign to metal post.
- Buried a silver deep-1 magnet on top of new monument for locating purposes.

LOCATION AND COMMENTS: Corner located about 6 feet South of a shallow field berm.

OREGON STATE PLANE CO-ORDINATES, Oregon North, NAD 83(91), International Feet:

N: 796342.65
E: 8712480.50

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla
V4N35J1

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

02-12-C