


History of original corner establishment:

This corner was originally established by William H. Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866. The original notes state that at the corner a post was set for the corner with a driven charred stake and pits and mounds constructed as per instructions.

In 1895, under County Survey No. 73, County Surveyor Kimbrell set a stone in the center of the North South road for the corner and also measured to the Southeast corner of Section 15.



N-15

Corner No.
 Compass Declination: 18.0°

Description of corner evidence found:

This corner position was re-established at the center of the existing North South road at the intersection point with a fence line extending East and a old fence berm and field line extending West. Additional measurements to the existing fence corner at the Southeast corner of Section 15 agree, within reason, with Kimbrell's 1895 measurements.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2" brass cap on a 1 1/4" galvanized iron pipe in the center of the road. The brass cap is located 6" below the paved road surface and is set in concrete with aluminum monument cover over the top of the brass cap monument.

Referenced the corner monument as follows:

A brass washer stamped PLS 1106 nailed to the West side of PP&L power pole no. 154001, 1' above ground, bears N 86 1/2°E 28.8'. Attached bearing object sign to the pole.

A brass washer stamped PLS 1106, nailed to the North side of PP&L power pole no. 224901, 1' above ground, bears S 07°E 187.2'. Attached bearing object sign to the pole.

The SW corner of the attached garage at the Perkins House bears S 31 1/2°E 137.0'.

A 2" channel iron, extending 4' above ground, bears N 58°W 26.3'.

Placed witness corner sign on fence corner East of the monument.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells

OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

Umatilla County Surveyor
 Date 10-91
 Rec'd By KK
 No. 91-79-R