


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P-9

History of original corner establishment:

The original corner was established by Wm. H. Odell on July 2, 1866, under GLO contract No. 114, as follows:

Set post with a charred stake, dug pits and mounds.



Description of corner evidence found:

The original corner position is lost.

Description of monument and accessories established to perpetuate the original location of this corner:

At the midpoint, between the Northwest and Southwest corners of section 21, I grout a 1" x 6" serrated and scored iron pipe. A 2 1/2" brass cap attached is marked as shown in the above diagram, from which:

A 5/8" x 30" rebar set 28" into the ground, with a red plastic cap stamped PLS 54871, bears N19°E, 66.5 feet.

A 5/8" x 30" rebar set 28" into the ground, with a red plastic cap stamped PLS 54871, bears S81°E, 22.1 feet.

A 5/8" x 30" rebar set 28" into the ground, with a red plastic cap stamped PLS 54871, bears S32°W, 43.0 feet.

A 5/8" x 30" rebar set 28" into the ground, with a red plastic cap stamped PLS 54871, bears N78°W, 29.6 feet.

I hereby certify the above corner point was perpetuated as hereon described on October 1, 2002. Bearings are true.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JANUARY 19, 1999
THOMAS S. FROST
54871

Office of _____ County of _____
State of _____
for record on the _____ day of _____

I hereby certify that the within instrument was filed in this office *Rawns 12-31-03*

(COUNTY OFFICIAL)

by

(DEPUTY)