

OREGON COUNTY RECORDED SURVEY FORM

COUNTY: Umatilla DATE: 05/14/97

CORNER DESIGNATION: V-1, The Northwest Corner of Section 31, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set post cor. for secs. 25, 30 & 31; drove charred stake, dug pits and raised mound as per instructions. Corner re-established by Z.F. Moody, GLO Contract No. 165, dated October 4, 1871. Notes state: Set post and made earth mound for cor. Secs. 31, 36, 25 & 30. Corner re-established by Jas. P. Currin and Jas. E. Noland, under Special Contract dated May 4, 1887. Notes state: Set a post, 48 x 4 x 4 ins., 12 ins. in the ground for Cor. to Secs. 30, 31, 25 & 36, marked R. 35 E., S. 30 on N.E., S. 31 on S.E., R. 34 E., S. 36 on SW., T. 4 N. S. 25 on NW. faces, with 5 notches on N., and 1 notch on S. edges. Dug pits, 18 x 18 x 12 ins., in each Sec. 5 1/2 ft. dist., raised a mound of earth, 2 ft. high, 4 1/2 ft. base around post.

A stone was established for the corner by Willard Bradley, County Surveyor, in April 1915, during Bradley's County Survey No. 406.

MONUMENT AND ACCESSORIES FOUND: None. This corner position was re-established by calculation, with reference to County Survey No. 406, by Willard Bradley, dated April 1915, after recovering the South 1/16 corner and Southeast corners of Section 31 as indicated on Bradley's Survey Plat.

MONUMENT MARKING DETAIL:

T4N  
R34E R35E  
S25 | S30  
S36 | S31  
1997  
PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on a 1" galvanized iron pipe 6" below ground surface, cap marked as shown in Monument Marking Detail.

Accessories:

A brass washer stamped "PLS 1106" nailed to Pacific Power and Light Pole #300101, bears N 08° E, 143.2 feet, with witness and bearing object signs attached.

A brass washer stamped "PLS 1106" nailed to Pacific Power and Light Pole #300000, bears S 03° E, 222.0 feet, with witness and bearing object signs attached.

A railroad spike stamped "PLS 1106" bears S 35° W, 38.6 feet.

A railroad spike stamped "PLS 1106" bears N 30° W, 39.9 feet.

Set steel fence post 5.6 feet East of brass cap with witness sign attached.

LOCATION & COMMENTS: Corner located on Pambrun Road at North end of private airstrip. Approximately 0.2 feet East of pavement.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Kelly Snively  
Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE  
FOR CORNER, NAD 83(91), INT. FEET:

N: 780430.11  
E: 8712876.56

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1997  
WILLIAM R. WELLS  
1106

Renews 6-30-98

97-141-C