

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/02/01

CORNER DESIGNATION: X-11, Center 1/4 corner Section 33, T4N., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: None.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT SET:

At corner position determined by survey, set 5/8 inch x 30 inch iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with cap buried 12 inches below ground for corner.

New Accessories:

A silver Deep-1 magnet marker, buried 18 inches in ground bears N 28° E, 40.2 feet. Bearing object sign is buried alongside of magnet.

A 5/8 inch by 30 inch iron rebar with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with cap buried 18 inches below ground bears S 70° E, 41.1 feet. Bearing object sign is buried alongside of rebar.

A brass washer stamped "PLS 1106" approximately 6 feet above ground in South face of a 24 inch diameter Locust, bears S 39 1/2° W, 69.3 feet, attached bearing object and witness sign to tree.

A 5/8 inch by 30 inch iron rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", cap set flush with ground in fence line at east edge of creek bears N 49 1/2° W, 59.7 feet. Attached bearing object sign to rebar and witness post sign to fence post 0.5 feet west of rebar in fence line.

LOCATION AND COMMENTS:

Corner is located at the edge of a farmed grass circle approximately 80 feet east of the centerline of creek and 10 feet west of edge of a irrigated grass circle.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Kevin Snively
4N34X11

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-02

RECEIVED BY

Umatilla County Surveyor

Date 04-01

Rec'd By JK

No. 01-52C