

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 06/13/01

CORNER DESIGNATION: A-11, North 1/4 Corner Section 4 only, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: None, corner was not originally established.

MONUMENT AND ACCESSORIES FOUND: None.

**MONUMENT MARKING DETAIL:**

T5N R35E

-----  
1/4 S4  
T4N R35E  
2001  
PLS 1106

**MONUMENT SET:**

At point determined by survey as shown on the accompanying Record of Survey, set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe, with cap buried 12" below ground level, marked as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, 18" below ground level, bears N 40° E, 33.1 feet.
  - A purple deep-1 magnet, 18" below ground level, bears S 40 1/2° E, 32.1 feet.
  - A blue deep-1 magnet, 18" below ground level, bears S 34° W, 34.3 feet.
  - An orange deep-1 magnet, 18" below ground level, bears N 34° W, 33.7 feet.
- Buried bearing object tag alongside the deep-1 magnets.

LOCATION AND COMMENTS: Corner is located about 3 feet North of South edge of Watts Road.

OREGON STATE PLANE CO-ORDINATES, North Zone, NAD 83(91), International Feet:

N: 806457.66  
E: 8725344.80

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT  
Mark Hammersla  
4N35A11

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-02*

02-12-C