

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/12/01

CORNER DESIGNATION: A-9, Northwest Corner of Section 4, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner established by Wm. H. Odell, Under Contract No. 114, Dated July 2nd, 1866. Record states: Set Closing Cor. for Secs. 4 & 5, drove charred stake, dug pits and raised mound as per instructions. Corner re-established on Umatilla County Survey No. M-120-B, by Krumbein Engineering LTD., dated December 1976. Survey No. M-120-B calls for setting a brass cap monument.

MONUMENT AND ACCESSORIES FOUND: Found bent, a 2 1/2" brass cap on galv. iron pipe witness corner monument, set by PLS 933, on North Side of East-West Road, (no record for this witness corner monument). Found corner monument from Survey No. M-120-B, buried 12" below ground in farmed field, 50 feet South of East-West Road. Note: Corner monument and witness monument per Survey No. M-120-B were not held, but are used as accessories to new corner monument set on this survey.

MONUMENT MARKING DETAIL:

T5N R35E
S32
S5 | S4
CC
T4N R35E
2001
PLS 1106

MONUMENT SET:

At point determined by single proportionate measurement as shown on the accompanying record of survey, set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe, with cap 8" below road surface, marked as shown in "Monument Marking Detail".

From which:

The 2 1/2" brass cap witness corner monument per Survey No. M-120-B, bears N 88° E, 190.0 feet (witness corner is bent, distance is to centerline of monument at ground level).

A purple deep-1 magnet, 18" below ground level, bears S 40 1/2° E, 50.2 feet. Buried bearing object sign with the deep-1 magnet.

The South top center end of an 18" diameter CMP culvert bears S 83° W, 90.8 feet.

The North top center end of same 18" CMP culvert bears N 82° W, 88.6 feet.

The brass cap monument set for the corner in Survey No. M-120-B bears S 71° 48'38" E, 169.55 feet.

Set steel fence post with witness post sign and bearing object sign attached, near brass cap witness monument per Survey No. M-120-B.

LOCATION AND COMMENTS: Corner is at a point approximately near visual centerline of Watts Road, a gravel road running East-West.

OREGON STATE PLANE CO-ORDINATES, North Zone, NAD 83(91), International Feet:

N: 806399.28
E: 8722696.08

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammersla

4N35A9

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

02-12-c