

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/14/01

CORNER DESIGNATION: C-5, the West 1/4 Corner of Section 5, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. H. Odell under Contract No. 114, dated July 2nd, 1866. Record states: Set post Cor. for 1/4 Sec., on side hill, facing the S., drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

## MONUMENT MARKING DETAIL:

T4N R35E  
1/4  
S6 | S5  
2001  
PLS 1106

## MONUMENT SET:

At point determined by single proportionate measure as shown on the accompanying Record of Survey, set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe 26" in the ground and surrounded with a mound of earth. Cap is marked as show in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, buried 16" in ground, bears N 68° E, 34.5 feet.
- A purple deep-1 magnet, buried 16" in ground, bears S 49° E, 35.3 feet.
- A 5/8" x 30" iron rebar with yellow plastic cap marked "OR PLS 1106 WA PLS 17372", with cap set 3" above ground bears S 51° W, 38.6 feet.
- An orange deep-1 magnet, buried 16" in ground, bears N 80° W, 26.0 feet.
- Buried bearing object signs alongside of deep-1 magnets. Attached bearing object sign to 5/8" rebar accessory.

LOCATION AND COMMENTS: Corner is located about 8' North of a field access road and 175' West of the County Road known as Lamar Gulch Road.

OREGON STATE PLANE CO-ORDINATES, Oregon North, NAD 83(91), International Feet:

N: 804689.25  
E: 8717412.05

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT  
Mark Hammersla  
4N35C5

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-02*

02-12-C