

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/13/01

CORNER DESIGNATION: C-9, West 1/4 Corner of Section 4, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Wm. H. Odell, under Contract No. 114, dated July 2nd, 1866. Record states: Set pot Cor. for 1/4 Sec., in small ravine, course S.W. drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N R35E
1/4
S5 | S4
2001
PLS 1106

MONUMENT SET:

At a point determined by single proportionate measurement as shown on the accompanying Record of Survey, set a 2" brass disk in concrete, 14" below ground, (a solid layer of basalt rock exists at this depth preventing setting monument any deeper), marked as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, 16" in the ground, bears N 50° E, 37.0 feet.
- A purple deep-1 magnet, 16" in the ground, bears S 27° E, 47.8 feet.
- A brass washer, stamped "OR PLS 1106", 2.0 feet above ground level, in a railroad tie fence corner post bears S 48° W, 66.2 feet.
- An orange deep-1 magnet, 16" in the ground, bears N 40 1/2° W, 38.9 feet.
- Buried bearing object signs with deep-1 magnets.
- Attached bearing object and "witness" signs to fence post.
- Set magnet above brass cap monument for locating purposes.

LOCATION AND COMMENTS: Corner is in a farmed field.

OREGON STATE PLANE CO-ORDINATES, North Zone, NAD 83(91), International Feet:

N: 804718.13
E: 8722714.50

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammersla
4N35C9

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

02-12-C