

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/08/01

CORNER DESIGNATION: E-5, Northwest Corner of Section 8, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. H. Odell under Contract No. 114, dated July 2nd, 1866. Record states: Set post Cor. for Secs. 5, 6, 7 & 8; drove charred stake and raised mound as per instructions. Corner was recovered John Kimbrell in Umatilla County Survey for A.L. Swagart recorded at Book 1 Page 347. Record states: Corner is a stone 22 x 5 x 5. Set on the West side of point of old cottonwood stake. Original.

MONUMENT AND ACCESSORIES FOUND: None, corner area falls near "cutbank" on East side of County Road..

MONUMENT MARKING DETAIL:

T4N R35E
S6 | S5
S7 | S8
2001
PLS 1106

MONUMENT SET:

At a point 1.85 chains East of a "spring branch", as called in John Kimbrell's notes, on the Easterly projection of an ancient fence crossing said "spring branch", set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe, with top 2 inches above ground level, stamped as shown in "Monument Marking Detail".

From which:

A 5/8" x 30" iron rebar with yellow plastic cap, 1 inch above ground level, bears N 22 1/2° E, 34.3 feet.

A 5/8" x 30" iron rebar with yellow plastic cap, 1 inch above ground level, bears S 31° E, 24.7 feet.

A steel fence post in East right-of-way fence line of County Road, (fourth steel fence post South of corner), bears S 04° W, 40.2 feet.

A steel fence post (second steel fence post North of corner) in East right-of-way fence of County Road bears N 12 1/2° W, 44.1 feet.

Attached bearing object tags to all accessories. Attached "witness" sign to wood fence post 8.0 feet West of corner monument. Yellow plastic caps are marked "OR PLS 1106 WA PLS 17372".

LOCATION AND COMMENTS: Corner approximately 25 feet East of from East edge of gravel road.

OREGON STATE PLANE CO-ORDINATES, North Zone, NAD 83(91), International Feet:



N: 802146.44
E: 8717481.29

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammersla

4N35E5



renews 6-30-02

02-12-e