

OREGON CORNER RESTORATION FORM

CORNER G-17

Section 10 Township 4N Range 35E.W.M.

County UMATILLA Date MARCH 8, 1991

CROSS REFERENCE:
MAP 91-17-C

CORNER DESIGNATION

$\frac{1}{4}$
S10/S11

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. THE ATHENA-BLUE MTN SECTION STATE HIGHWAY MAP (DWG BB-10-25 DATED JUNE & NOV. 1960) SHOWS A STATE PLANE CO-ORDINATE FOR CORNER - NO MONUMENT INDICATED
Monument(s) & Accessories Found: (Condition and Source)

NONE. THE CORNER AREA HAS BEEN FARMED EXTENSIVELY AND ALL FENCES IN THE AREA HAVE BEEN REMOVED.

NOTE: THIS CORNER WAS ORIGINALLY ESTABLISHED BY W.M. H. ODELL, UNDER CONTRACT NO. 114 DATED JULY 2, 1866. ORIGINAL NOTES CALL FOR A POST WITH CHARRED STAKE, PITS AND MOUND.

Monument Detail

SET $2\frac{1}{2}$ " BRASS CAP ON $\frac{1}{4}$ " BY 30" GALV. IRON PIPE WITH TOP OF CAP BURIED 18" BELOW GROUND LINE. SET STEEL FENCE POST $3\frac{1}{2}$ ' NORTH OF CORNER AND ATTACHED WITNESS COR. SIGN.

Sketch
CAP MARKED:
T4N R35E

$\frac{1}{4}$
S10/S11
1991
PLS1106

Monument Set (Procedures and Description)

AFTER LOCATING CERTAIN EXISTING STATE HIGHWAY MONUMENTS AND DETERMINING THEIR STATE PLANE CO-ORDINATE BASIS, I RE-ESTABLISHED THIS CORNER BASED ON STATE HIGHWAY TIE AS SHOWN ON STATE MAP (DWG BB-10-25).

- ① New Accessories
- ① ALUM. NAIL WITH PLS 1106 WASHER NAILED TO EAST SIDE OF MOST SLY 12" DECIDUOUS TREE IN N-S LINE OF TREES BEARS N $18\frac{1}{2}^{\circ}$ E - 158.6 FT.
- ② ALUM. NAIL WITH PLS 1106 WASHER NAILED TO EAST SIDE OF 18" DECIDUOUS TREE BEARS S 67° W - 106.3 FT.
- ③ CENTERLINE OF AN 8" WELL CASING BEARS S 04° E 306.2 FT.
- ④ $\frac{5}{8}$ " PIN AT ENGR'S CENTERLINE STATION 1094400 ON THE WEST SIDE (R/W) OF STATE HWY 11 BEARS N $67^{\circ}55'45"$ W - 208.35 FT. ATTACHED BEARING OBJECT SIGNS TO THE 2 TREE REFERENCES AND TO A POWER POLE 3' WEST OF THE $\frac{5}{8}$ " PIN.

Location & Comments

CORNER LOCATED IN ACTIVE GRAIN FIELD
LOOK FOR BEARING
OBJECT SIGNS NEARBY

Compass Declination 18 $^{\circ}$
Firm/Agency WILLIAM R. WELLS, PLS
Address P.O. BOX 1696
PENDLETON, OR 97801

Party Chief BILL WELLS

Notes _____

Witness BILL QUAMPT

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

RECEIVED BY

Jmatilla County Surveyor

Date 3-9-91

led'd by KA

to 91-17-C