

T 4N, R 35E., W.M.

Corner Code No. J-13


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 714, dated 2 July, 1866. The original notes state:

Set post Cor. for Secs. 9, 10, 15 & 16; drove charred stake, dug pits and raised mound as per instructions.

As noted on Survey Map No. 83-76-C, this corner was re-established and monumented in 1983, based on Railroad ties.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

None, this corner has been removed by ditch construction along the County Road. The position of this corner was re-established by proportional measurement between the South 1/4 of Section 9 and the South 1/4 of Section 10. The basis of proportional measurement were those distances shown on Survey Map No. 83-76-C. The record angle from Survey Map No. 83-76-C was held at the Southeast corner of Section 9.

Description of monument and accessories established to perpetuate the original location of this corner:

At the re-established corner position, set a 2 1/2" brass cap on 1 1/4" by 30" galvanized iron pipe, with top of brass cap 6" below existing ditch line.

Referenced the monument as follows:

The Southeast corner of the concrete bridge wing wall on the East side of Pine Creek bears S 83°55' E 205.9'.

A 3/4" brass washer, nailed to the Northwest corner of a white shed, about 1' above ground, bears S 69°40' E 43.4'.

A 3/4" brass washer, nailed to the North side of phone pole No. 283, 1' above ground, bears S 66°59' E 10.6'. Placed bearing object sign on pole.

A 3/4" brass washer, nailed to the North side of power pole No. 169901, 1' above ground, bears S 85°58' W 51.2'. Placed bearing object sign on pole.

Set steel fence post 4' South of corner and attached witness corner sign.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Expires 12-31-94

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 5-93

Rec'd By KK

No. 93-42-B