

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/07/01

CORNER DESIGNATION: L-17, East 1/4 Corner Section 15, T4N., R35E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. H. Odell under Contract No. 114, dated July 2nd, 1866. Record states: Set 1/4 Sec. post Cor.; drove charred stake, dug pits and raised mound as per instructions. Corner called as found in Survey recorded in Book 1, Page 496, Umatilla County Survey Records, by John W. Kimbrell, dated March 25, 1903.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N R35E
1/4
S15 | S14
2001
PLS 1106

MONUMENT SET:

Re-established corner position between recovered or re-established Northeast and Southeast Corners of Section 15, holding location of East-West field berm for latitude, as shown on accompanying Record of Survey. Set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe with cap buried 16" below ground level, stamped as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, buried 16" in ground, bears N 43 1/2° E, 31.5 feet.
 - A purple deep-1 magnet, buried 16" in ground, bears S 32° E, 31.1 feet.
 - A blue deep-1 magnet, buried 16" in ground, bears S 50° W, 29.2 feet.
 - An orange deep-1 magnet, buried 16" in ground, bears N 35° W, 30.3 feet.
- Buried bearing object signs alongside of deep-1 magnets.

LOCATION AND COMMENTS: Corner is located in a East-West field berm.

OREGON STATE PLANE CO-ORDINATES, Oregon North, NAD 83(91), International Feet:

N: 794176.54
E: 8733568.78

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammersla
V4N35L17

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

02-12c