

OREGON CORNER RELOCATION FORM

COUNTY: Umatilla DATE: 03/05/97

CORNER DESIGNATION: N-1, The Northwest Corner of Section 19, T4N., R35E., W.M. N-1

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by William H. Odell, GLO Contract No. 114, dated July 2, 1866. Survey notes state: Set post cor. for Secs. 13, 24, 18 & 19; drove charred stake, dug pits and raised mound as per instructions. Corner re-established by PLS 933, Umatilla County Record No. I-143-A, dated September 1974.

MONUMENT AND ACCESSORIES FOUND: Found a 2 1/2" brass cap on galvanized iron pipe 0.4 feet above ground surface. Steel fence post 0.8 feet South with witness sign attached. A 2 1/2" brass cap on galvanized iron pipe witness corner 0.3 feet above ground surface, bears North 36° East, 41.52 feet. Steel fence post 0.8 feet Northwest of witness corner.

MONUMENT MARKING DETAIL:

Corner	Umatilla County	Witness Corner	Umatilla County
Monument:	T4N	Monument:	T4N
	R34E R35E		R34E R35E
	S13 S18		S13 S18
	S24 S19		S24 S19
	1974		1974 NE 41.52
	PLS 933		PLS 933
	Surveyor		Surveyor

MONUMENT SET: Existing monument.

New Accessories:

A brass washer stamped "PLS 1106" on the North side of Pacific Power and Light Pole #249900, 2.4 feet from ground surface, bears S 54° E, 4.5 feet, with bearing object and witness sign attached. A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears S 75° W, 16.3 feet, with a steel fence post nearby with bearing object and witness signs attached. A brass washer stamped "PLS 1106" on the West side of a red and white railroad tie, 1.0 feet above ground, bears N 36° W, 42.1 feet, with bearing object and witness sign attached.

LOCATION & COMMENTS: Corner South of Sherman Street near air strip in Athena.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Kelly Snively
Troy Baker

OREGON NORTH STATE PLANE CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 791045.18
E: 8712667.45

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renew 6-30-98