

OREGON CORNER RELOCATION FORM

COUNTY: Umatilla DATE: 03/04/97

CORNER DESIGNATION: N-11, The North Quarter Corner of Section 21, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by William H. Odell, GLO Contract No. 114, dated July 2, 1866. Survey notes state: Set 1/4 Sec. post Cor.; drove charred stake, dug pits and raised mound as per instructions. Corner re-established by PLS 933, Umatilla County Survey No. 83-156-C. Notes state: K.E.L. set B.C. at computed position from information on Co. Survey Drwg No. Q-716-A.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2 inch brass cap on galvanized iron pipe, 1.0 foot below surface of North-South Schrimpf Road.

MONUMENT MARKING DETAIL:

Umatilla County
T4N R35E
1 S16
4 S21
1983
PLS 933
Surveyor

MONUMENT SET: Existing monument.

New Accessories:

A 5/8" x 30" iron pin with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 32 1/2° E, 49.9 feet.

A 5/8" x 30" iron pin with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 28° E, 54.2 feet.

A 5/8" x 30" iron pin with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 07° W, 48.7 feet.

A 5/8" x 30" iron pin with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 02 1/2° W, 44.1 feet.

All iron pins have bearing object signs attached and a steel fence post nearby with a witness sign attached.

LOCATION & COMMENTS: Corner in Schrimpf Road, at the easterly projection of an old field berm.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Kelly Snively
Troy Baker

OREGON NORTH STATE PLANE CO-ORDINATE
FOR CORNER, NAD 83(91), INT. FEET:

N: 791505.88
E: 8725675.18

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98