

COUNTY: Umatilla DATE: 03/05/97

CORNER DESIGNATION: N-3, The North Quarter Corner of Section 19, T4N., R35E., W.M.

N-3

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by William H. Odell, GLO Contract No. 114, dated July 2, 1866. Survey notes state: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions. Corner re-monumented by PLS 933, Umatilla County Survey No.83-156-C. Notes state: K.E.L. found stone, Co. Survey Drwg. No's K-69A & S-149, removed stone, and set B.C. K.E.C. found stone with "+".

MONUMENT AND ACCESSORIES FOUND: Found railroad spike 0.2 feet under asphalt and two witness corners, both 2 1/2" brass caps on iron pipes.

Note: Railroad spike is believed to be set above the brass cap monument set per County Survey No. 83-156-C.

MONUMENT MARKING DETAIL:

Witness Corner:

T4N R35E
W.C. SE 39.11ft
1 S18
4 S19
1981
PLS 933

This cap is level with the ground, with witness and bearing object signs attached to PPL #194960 bears S61°E, 39.11' from corner

Witness Corner:

T4N R35E
W.C. NE 47.58ft
1 S18
4 S19
1981
PLS 933

This cap is 0.6 feet above ground with witness and bearing object signs on short telephone pole. bears N61°E, 47.58' from corner.

MONUMENT SET: Existing monument.

New Accessories:

A brass washer stamped "PLS 1106" on Pacific Power and Light Pole 1.0 feet from ground surface, bears S 74° W, 59.8 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears N 53° W, 41.3 feet, steel fence post nearby with witness sign attached.

Bearing object signs attached to PP&L pole and iron rod.

LOCATION & COMMENTS: Corner is railroad spike in the middle of Sherman Street in Athena.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively
Troy Baker

OREGON NORTH STATE PLANE CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 791117.71

E: 8715098.04

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98

97-141-C