

OREGON CORNER RE-LOCATION FORM

COUNTY: Umatilla DATE: 06/06/97

CORNER DESIGNATION: N-9, The Northwest Corner of Section 21, T4N., R35E., W.M.  
 PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by William H. Odell, GLO Contract No. 114, dated July 2, 1866. Survey notes state: Set post Cor. for Secs. 16, 17, 20 & 21; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. This corner position was re-established by railroad tie information detailed on Umatilla County Partition Plat No. 1995-29. Using information shown on Umatilla County Partition Plat 1995-29, I calculated the location of the corner, which falls in the traveled and maintenance corridor of Highway 11.

MONUMENT MARKING DETAIL:

W.C.  
 120 FT  
 ←-----  
 T4N R35E  
 S17|S16  
 S20|S21  
 1997  
 PLS 1106

MONUMENT SET:

At a point S 89°57'44" E, 120.02' from true corner point, set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe, 28" in the ground, marked as shown in monument marking detail. This monument is a witness corner.

New Accessories; from witness corner:

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 38° E, 29.6 feet.  
 A 5/8" nut and bolt on snow barrier bears S 68° E, 51.2 feet.  
 A 5/8" nut and bolt on snow barrier bears S 17° W, 68.2 feet.  
 A 5/8" x 24" iron pin with 1 1/2" yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 89°57'44" W, 240.04 feet from witness corner and N 89°57'44" W, 120.02 feet from true corner point.  
 Bearing object signs attached to all iron rods and snow barrier bolts.  
 Steel fence post approximately 5 feet North of monument with witness sign attached.

LOCATION & COMMENTS: Witness corner is located South of Highway 11 and is visible from the road.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Kelly Snively  
 Jason Wells

OREGON NORTH STATE PLANE CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

For true corner: N: 791440.28  
 E: 8723011.58  
 For witness corner: N: 791443.23  
 E: 8723131.54

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*William R. Wells*

OREGON  
 JULY 22, 1977  
 WILLIAM R. WELLS  
 1106

Renews 6-30-98

97-141-C