

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/09/97

CORNER DESIGNATION: P-13, The East Quarter Corner of Section 21, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions. The line through this 1/4 corner was retraced by Arnold in 1889 during the survey to subdivide Section 16, reported in Record of Private surveys Book 1, Pages 221-225. The corner was not recovered.

MONUMENT AND ACCESSORIES FOUND: None. Re-established corner by single proportion measurement between the Northwest and Southwest corners of Section 22, with reference to distances reported by Arnold in his survey to subdivide Section 16, dated 1889, and reported in Record of Private Surveys Book 1, Pages 221-225.

MONUMENT MARKING DETAIL:

T4N R35E  
1  
4  
S21 | S22  
1997  
PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe 18 inches below surface of cultivated field, monument marked as shown in monument marking detail.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 37° E, 17.8 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 29° E, 18.1 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 47° W, 19.0 feet.

A 5/8" x 24" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 19° W, 18.2 feet.

Attached bearing object signs to all iron rods.

LOCATION & COMMENTS: Corner located in cultivated field.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Kelly Snively  
Jason Wells

OREGON NORTH STATE PLANE CO-ORDINATE  
FOR CORNER, NAD 83(91), INT. FEET:

N: 788886.68  
E: 8728432.51

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-98*