

OREGON CORNER RE-ESTABLISHMENT FORM

COUNTY: Umatilla DATE: 06/10/97

CORNER DESIGNATION: P-17, The West Quarter Corner of Section 23, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by William H. Odell, GLO Contract No. 114, dated July 2, 1866. Survey notes state: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions. Corner was recovered and remonumented with a stone monument by Arnold, in 1887, County Survey No. 25.

MONUMENT AND ACCESSORIES FOUND: None. Re-established corner by single proportionate measure between the Northeast and Southeast corners of Section 22 using the distance record by Arnold as reported on County Survey No. 25, dated 1887.

MONUMENT MARKING DETAIL:

Corner Monument:

T4N R35E  
1  
4  
S22 | S23  
1997  
PLS 1106

Witness Corner:

T4N R35E  
1 WC  
4  
S22 | S23  
1997  
PLS 1106  
32.97'

MONUMENT SET:

A 2 1/2" brass cap on a 1" x 30" galvanized iron pipe, 20" below surface of cultivated field, marked as shown in monument marking detail.

New Accessories:

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 61° E, 16.7 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 27° E, 26.1 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 21° W, 27.0 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 60° W, 18.7 feet.

All iron rods have bearing object signs attached.

A 2 1/2" brass cap on a 1" x 30" galvanized iron pipe witness corner with top of cap buried 20" below field line bears S 00°36'04" E, 32.97'. Cap marked as shown in corner diagram.

LOCATION & COMMENTS: Corner falls in cultivated field with no remaining evidence of field lines, fences or roads.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively  
Jason Wells

OREGON NORTH STATE PLANE CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 789046.42  
E: 8733755.06

REGISTERED PROFESSIONAL LAND SURVEYOR

Will R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Renews 6-30-98

97-141-C