

COUNTY: Umatilla DATE: 06/19/97

CORNER DESIGNATION: V-11, The North Quarter Corner of Section 33, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set 1/4 Sec. post Cor.; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner position was established on line between the Northwest and Northeast corners of Section 33 and the intersection of North-South field line.

MONUMENT MARKING DETAIL:

T4N R35E
1 S28
4 S33
1997
PLS 1106

MONUMENT SET:

A 2 1/2" brass cap on a 1" x 30" galvanized iron pipe 18" below the surface of a cultivated field.
A 5/8" x 30" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 25° E, 12.7 feet.
A 5/8" x 30" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 22° E, 14.9 feet.
A 5/8" x 30" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 37° W, 17.5 feet.
A 5/8" x 30" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 44° W, 18.3 feet.
All iron rods have bearing object tags attached and are 18" below the surface of a cultivated field.

LOCATION & COMMENTS: Corner is located approximately 1/2 mile South of Key Cemetery in field line.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Kelly Snively
Troy Baker

OREGON STATE PLANE NORTH CO-ORDINATE
FOR CORNER, NAD 83(91), INT. FEET:

N: 780801.96
E: 8725891.14

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98

97-141-C