

OREGON CORNER RELOCATION FORM

COUNTY: Umatilla DATE: 03/04/97

CORNER DESIGNATION: V-13, The Northwest Corner of Section 34, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set post Cor. for Secs. 27, 28, 33 & 34; drove charred stake, and raised mound as per instructions.

Corner re-established by PLS 933, Umatilla County Survey No. 83-156-C. Notes state: K.E.L. set B.C. at intersection of plow lines running East-West and centerline of county road running North-South. Set steel post with survey marker sign 40.0' West and steel post with B.O. sign 20.0' East.

MONUMENT AND ACCESSORIES FOUND: Found a 2 1/2" brass cap on a galvanized iron pipe 1.0 feet below surface of County Road heading North-South. (marked as shown below)

MONUMENT MARKING DETAIL:

Umatilla County  
S28 | S27  
S33 | S34  
1983  
PLS 933  
Surveyor

MONUMENT SET: Existing monument.

New Accessories:

A 5/8" x 30" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 26° E, 45.4 feet.

A 5/8" x 30" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 24° E, 40.7 feet.

A 5/8" x 30" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 20° W, 39.3 feet.

A 5/8" x 30" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 16° W, 41.2 feet.

All iron rods have bearing object tags attached and steel fence posts nearby with witness signs attached.

Set steel fence post 10.0 feet West of brass cap with witness sign attached.

LOCATION & COMMENTS: Below surface of county road running North-South, in line with edge of wheatfields running East-West.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Kelly Snively  
Troy Baker

OREGON STATE PLANE NORTH CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 780904.50  
E: 8728620.63

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-98*