

OREGON CORNER RELOCATION FORM

COUNTY: Umatilla DATE: 06/19/97

CORNER DESIGNATION: V-9, The Northwest Corner of Section 33, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set post Cor. for Secs. 28, 29, 32 & 33; drove charred stake, dug pits and raised mound as per instructions. John Kimbrell, County Surveyor, recovered "old corner" in survey reported in Record of Private Surveys, Book 1, Page 474, dated October 1901.

MONUMENT AND ACCESSORIES FOUND: None. This corner was re-established by double proportionate measure using the Odell distance record along the North line of Section 33 and from the West Quarter Corner of Section 28, the Currin and Noland distance record along the North line of Section 32 and the distance record by John Kimbrell, County Surveyor, as reported in Record of Private Surveys, Book 1, Page 474, for the West line of Section 33.

MONUMENT MARKING DETAIL:

T4N R35E  
S29 | S28  
S32 | S33  
1997  
PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe 18" below surface of cultivated field, cap marked as shown in Monument Marking Detail.

Accessories:

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 44° E, 15.4 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 37° E, 15.0 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 42° W, 19.0 feet.

A 5/8" x 24" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears N 53° W, 15.0 feet.

All iron rods are 18" below ground surface of cultivated field with bearing object tags attached.

Note: Monument is located in middle of cultivated field, no physical references within 1/2 mile.

LOCATION & COMMENTS: Located in cultivated field.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Kelly Snively  
Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE  
FOR CORNER, NAD 83(91), INT. FEET:

N: 780701.75  
E: 8723223.63

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Renews 6-30-98

97-141-C