

OREGON COR. R RE ORATION FORM

COUNTY: Umatilla DATE: 06/12/97

CORNER DESIGNATION: X-13, The East Quarter Corner of Section 33, T4N., R35E., W.M.  
PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set post Cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner re-established at centerline of a three way road intersection with roads extending North-South and East.

MONUMENT MARKING DETAIL:

T4N R35E  
1  
4  
S33 | S34  
1997  
PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on a 1" x 30" galvanized iron pipe 8 inches below the surface of gravel road, monument marked as shown in monument marking detail.  
An iron pipe bears N 65° E, 47.4 feet.  
An underground cable sign post bears S 50° E, 39.0 feet.  
A road sign post bears S 87° W, 13.1 feet.  
A 4" galvanized post bears N 12° W, 44.0 feet.  
Attached bearing object signs to all bearing objects.  
The road sign post and galvanized post have witness signs attached.

LOCATION & COMMENTS: Monument is located in the intersection of Woods Road and Degraw Road.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Kelly Snively  
Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE FOR CORNER, NAD 83(91), INT. FEET:

N: 778243.22  
E: 8728644.22

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Renews 6-30-98