

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E., W.M.

Corner Code No. R-3


Notes: Monument marked as shown below

**History of original corner establishment:**

This corner was originally established by William Odell, U. S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866. The original notes state that at the corner a post was set for the corner from which:

A 24" pine bears N11°W 67 lks.  
A 20" pine bears S25°W 130 lks.

In 1889, during his County Survey No. 46, surveyor Arnold found the original wood post and re-monumented it with a basalt stone. Arnold also marked a new bearing tree:  
A 12" pine bears S49°30'W 11' scribed 1/4 S BT CS.



Corner No.  
Compass Declination: 19.0°

**Description of corner evidence found:**

Found a 13" by 11" by 3" basalt stone, lying flat, marked "1/4" on top. The stone found is located S55°E 3', from a fence corner with fences going east, northwest and south.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

At the position of the found stone, set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe, 28" in the ground and surrounded with a mound of earth. Placed stone in the new mound. From the new monument:

A 24" ponderosa pine bears S39°E 24.2' scribed 1/4 S30 BT.  
A 18" ponderosa pine bears N55°E 15.0' scribed 1/4 S19 BT.

Bearing trees have bearing object signs attached to them.

Set steel fence post north of corner and attached witness corner sign.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

7-27-88

Office of Survey County of Umatilla  
State of OR, I hereby certify that the within instrument was filed in this office  
for record on the 28<sup>th</sup> day of July, 1988  
David H. Krumboltz by Kathleen Amsberg  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 7-88  
Rec'd By [Signature]  
No. 88-412-C

GPO-799-876