

CE...FIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E., W.M.

Corner Code No. V-1


Note: Monument marked as shown below

**History of original corner establishment:**

This corner was originally established by Odell and Lewis, U.S. Deputy Surveyors, under Contract No. 110, dated February 7, 1863. The original notes state that at the corner a wood post was set with charred stake, earth mound and pits.

In 1889, during his County Survey No. 46, Surveyor Arnold found the corner and states in his original notes:

"I find the S.W. cor. of sec. 30, in the same place, as when found by me Aug. 1878, at which time the original charred post was found, with mound and pits, and verified by Chas. Mc Morris".



Corner No.  
Compass Declination 19.0°

**Description of corner evidence found:**

Found mound of stone at fence corner with fences running S48°E and south from corner point.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

At the position of the found rock mound and fence corner, set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe, 24" in the ground and surrounded with a mound of earth and stone. Set reference monuments referencing the corner as follows:

A 1 1/2" plastic cap, marked "W.R. Wells, PLS 1106", set on a 5/8" by 30" iron pin, bears S48°E 26.4'. Set steel fence post near reference monument with bearing object sign attached.  
A 1 1/2" aluminum cap, marked as shown below, set on a 5/8" by 30" iron pin bears S2°W 23.4'. Set steel fence post with bearing object sign next to reference monument.

Set steel fence post north of corner with witness corner sign attached.

The aluminum cap on the reference monument is marked:

R M  
23.4 Ft  
←  
NW COR  
S31  
1106

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

7-27-88

Office of Survey County of Umatilla  
State of Oregon. I hereby certify that the within instrument was filed in this office for record on the 27 day of July, 1988  
David H. Hundert by Kathleen Ambrose  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 7-88  
Rec'd By [Signature]  
No. 88-42-88

GPO-786-876