


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

This corner was originally established by William Odell under contract No. 114 dated July 2, 1866. The original notes state that at the corner a wooden post was set from which:

- A 24" Pine bears S25°E - 97 lk (64.0 ft)
- A 30" Pine bears S45°W - 47 lk (31.0 ft)
- A 20" Pine bears N30°W - 89 lk (58.7 ft)
- A 24" Pine bears N40°E - 79 lk (52.1 ft)



V-19

V-17


Description of corner evidence found:

A few stones near fence corner.
 A 36 inch pine stump bears S41°W - 31.0 ft, scribing "BT" visible after opening old blaze, remainder of scribing rotted away.
 A 24 inch rotted pine stump bears S30°E - 64.0 feet - no visible scribing left.
 No evidence of BT's remain in the NW & NE quadrants (area farmed). The corner position was re-established by measuring record distances from center of existing BT stumps in the SW & SE quadrants.
 The re-established corner falls approximately 1.0 feet South of an old fence corner, fences go East and South.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner position a 2"x30" iron pipe with brass cap was set 15 inches in the ground with a mound of stones surrounding the pipe. Set steel fence post next to the corner monument.

The brass cap is marked:



This corner was set December 18, 1979.

REGISTERED PROFESSIONAL LAND SURVEYOR <i>William R. Wells</i> OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of Surveyor County of Umatilla
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 28th day of FEBRUARY 1980
David Krumboltz by Betty J. Shatto
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
12 GPO - 798-276
 Umatilla County Surveyor
 Date 2-28-80
 Rec'd By BL Shatto
 No. R-29-