

CELEBRATED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E., W.M.

Corner Code No. V-9


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by William Opell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866. The original notes state that at the corner a wood post was set on the prairie, with charred stake, earth mound and pits.

In 1897, during his Co. Survey No. 97, John Kimbrell recovers and surveys through the corner during his survey of Section 32. Kimbrell notes that the corner is a "gate" said by old settlers to be the corner.

On a state highway map, located in the Pendleton Office of the Highway Department, there is a call to a stone being found for the corner. The map also shows a state plane coordinate for the corner and a state plane coordinate for the East 1/4 corner of Section 29.



Corner No.
Compass Declination: 19.0°

Description of corner evidence found:

None. This corner was reestablished by double proportion measure between the North 1/4 corner of Sec. 31 to the west, the North 1/4 corner of Sec. 33 to the east, the east 1/4 corner of Section 29 to the north and and east 1/4 corner of Sec. 32 to the south, using record measurements of the 1897 Kimbrell survey.

Based on state highway division ties previously described in corner history, a search was made for the "stone". Several stones were found near the corner position but none could be identified as a corner stone. No record was found of a stone ever being set to monument this corner. It is noted that the distance tie reported on the highway map, matches the computed distance within 2 feet but the bearing reported by the highway map (after converting grid bearing to true bearing) is substantially different. The computed corner falls in the edge of a north-south road, and the stone, if it did represent the corner, has probably been graded out.

Description of monument and accessories established to perpetuate the original location of this corner:

At the computed corner position, set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe, 40" in the ground. The top of the cap on the monument is buried 10" below ground in the west edge of a north-south road. Referenced the monument with reference monuments as follows:

A 1 1/2" plastic cap, marked "W.R. Wells, PLS 1106", set on a 5/8" by 30" iron pin bears N55°W 7.00'. Attached bearing object sign to steel fence post near the reference monument.

A 1 1/2" plastic cap, marked "W.R. Wells, PLS 1106", set on a 5/8" by 30" iron pin bears 831°W 11.15'. Attached bearing object sign to steel fence post near the reference monument.

The reference monuments are set in a north-south fence line on the west side of a north-south gravel road.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

7-27-88

Office of Survey County of Umatilla
State of Ore., I hereby certify that the within instrument was filed in this office
for record on the 28th day of July, 1988
David H. Kumbert by William R. Wells
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surv- 968 690-700-876

Date 7-88
Rec'd By ST
No. 88-42-C