

CELESTIAL RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E., W.M.


Corner Code No. X-17

Notes: Monument marked as shown below

History of original corner establishment:

This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866. The original notes state that at the corner a wood post was set for the corner from which:

A 3 1/2" pine bears S60°W 26 lks.
A 10" pine bears N62°E 18 lks.



Corner No.
Compass Declination: 19.0°

Description of corner evidence found:

None, except for fence lines.

Description of monument and accessories established to perpetuate the original location of this corner:

Reestablished corner at the intersection of the Southerly projection of an old fence running South from the Northeast corner of Section 34, (fence is visible North of Pine Creek), and an East-West fence. At the reestablished corner position, I set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe, 29" in the ground. From the reestablished corner monument:

A 19" ponderosa pine bears N71°E 48.3'.
A 17" ponderosa pine bears S27°W 87.4'.

Bearing trees have a bearing object sign attached to them. Set a steel fence post 9.5' East of corner and attached a witness corner sign and a bearing object sign.

The reestablished corner position matches physical improvements in the area including the west edge of the cleared pasture to the south. There are two east-west fences in the area, an older fence and a new fence. The corner was reestablished based on the position of the old fence east and west of the reestablished corner position.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

7-27-88

Office of Survey County of Umatilla
State of OR I hereby certify that the within instrument was filed in this office
for record on the 25th day of July 1988
David G. Kumbert by William R. Wells
(COUNTY OFFICIAL) (DEPUTY) **RECEIVED BY**

Umatilla County Surveyor
Date 7-88 GPO-700-876
Rec'd By JA
No. 88-42-C