

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


T 4N, R 36E., W.M.

Corner Code No. Z-11

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by Odell and Lewis, U.S. Deputy Surveyors, under Contract No. 110, dated February 7, 1865. The original notes state that at the corner a wood post was set from which
 A 36" pine bears South 7 lks.
 A 24" pine bears N85°W 80 lks.



Corner No.
Compass Declination: 19.0°

Description of corner evidence found:

Afer an extensive search, found the southerly bearing tree, a burnt, down 38" ponderosa pine snag, badly rotted. This tree was determined to be the southerly bearing tree from axe marks and evidence of the burnt out blaze. There are old square nails in this tree with pieces of a old wood rail fence still attached to the nails. There is a newer north-south fence about 20' north of corner position and a strand of wire from an old east-west fence on the bearing tree. The corner falls on a very steep, rocky hillside.

Description of monument and accessories I established to perpetuate the original location of this corner:

At a point North 4.6 feet from the root hole of the Southerly bearing tree, set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe 20" in the ground to bedrock and surrounded with a mound of earth and stone from which:

A 16" ponderosa pine bears S68°E 55.0' scribed 1/4 S4 BT.
 A 2 1/2" by 2" by 1 1/2" out of ground, rock in place bears N46°E 58.7' marked "X B0" on Southwest face.

Attached bearing object sign to bearing tree and set steel fence post west of corner and attached witness corner sign.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

7-27-88

Office of Jurgen County of Umatilla
 State of OR, I hereby certify that the within instrument was filed in this office
 for record on the 28th day of July, 1988
David H. Krambs by Kathleen K. Ambrose
 (COUNTY OFFICIAL) (DEPUTY)

Umatilla County Surveyor

Date 7-88 OPD-788-278

Rec'd by [Signature]

No. 88-42-C