

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 36E., W.M.


Corner Code No. Z-15

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by Odell and Lewis, U.S. Deputy Surveyors, under Contract No. 110, dated February 7, 1865. The original notes state that at the corner a wood post was set from which:

A 4" larch bears 88°E 18 lks.
A 3" larch bears N15°W 13 lks.



Corner No.
Compass Declination: 19.0°

Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

Reestablished the corner position by single proportion measure between the Southwest and Southeast corners of Section 34. At the reestablished corner position, set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe, 24" in the ground and surrounded with a mound of earth and stone from which:

A 18" douglas fir bears N57°E 103.6' scribed 1/4 S34 BT.
A 10" white fir bears S28°E 21.2' scribed 1/4 S3 BT.

Attached bearing object signs to each of the bearing trees and set a steel fence post East of the corner and attached a witness corner sign.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

7-27-88

Office of Survey County of Umatilla
 State of OR I hereby certify that the within instrument was filed in this office
 for record on the 28th day of July 1988
David H. Kumbain by Kathleen K. Ambrose
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

Umatilla County Survey
 Date 7-88
 Rec'd By KA
 No. 88-42-C