

C L A S S I F I E D R E C O R D O F L A N D C O R N E R M O N U M E N T A T I O N

T 4N, R 36E . , W.M.


Corner Code No. Z-5

Note: Monument marked as shown below

**History of original corner establishment:**

This corner was originally established by Odell and Lewis, U.S. Deputy Surveyors, under Contract No. 110, dated February 7, 1865. The original notes state that at the corner a wood post was set from which:

- A 12" pine bears N88°E 94 1/2 kts.
- A 12" pine bears S85°E 99 1/2 kts.
- A 12" pine bears S55°W 12 1/2 kts.
- A 12" pine bears N78°W 63 kts.



Corner No.  
Compass Declination: 19.0°

**Description of corner evidence found:**

Uprooted Section 6 bearing tree, now a 15" ponderosa pine snag, 15' long, with full scribes on upper and lower blazes. There is also and uprooted, rotted, ponderosa pine in approximately the correct position to be the Section 32 bearing tree.

**Description of monument and accessories established to perpetuate the original location of this corner:**

At a point N35°E 7.9' from the root hole of the Section 6 bearing tree, set a 2 1/2" brass cap on a 1 1/2" by 30" galv. iron pipe 24" in the ground and surrounded with a mound of earth from which:

- A 17" douglas fir bears N39°E 11.9' scribed T4N R36E S32 BT.
- A 16" douglas fir bears N11°W 19.0' scribed T4N R36E S31 BT.

No trees are convenient for reference to the south.

Placed bearing object sign on each of the bearing trees and set a steel fence post west of the corner and attached witness corner sign.

This corner falls in an east-west fence on a steep, brushy, north slope.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1988  
WILLIAM R. WELLS  
1106

7-27-88

Office of Survey County of Umatilla  
 State of OR I hereby certify that the within instrument was filed in this office  
 for record on the 28<sup>th</sup> day of July 1988  
David H. Kumbert by Kathleen K. Amstrong  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
 Umatilla County Surveyor  
 Date 7-88  
 Rec'd By HA  
 No. 88-42-C

690-700-270