

Index

File No. E-25

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. _____

Cor.

No. _____

T 4 N R. 37 E

R.D. Walla Walla


County Umatilla

Merid. Willamette

N.F. Umatilla

State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

No trace of original monumentations.

THIS CORNER WAS SEARCHED FOR A TOTAL OF 2 1/2 HOURS WITH A 2 PERSON CREW, WITHOUT SUCCESS.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. 880-49

Filed At. Umatilla, S.O.

Object Ident. Trees

Ident. By WR Wells

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is located on very steep, rocky West facing slope about 150' West of ridgetop.

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

Signature

Walter R. Wells

Title

Land Surveyor

Division

Headquarters

Pendleton, Or.

Date

9-01-88

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Corner was re-established by modified single proportion measure as described in section 5-36 of the 1973 "Manual". Corners used for control were the found East 1/4 corner of Sec.12, T4N R37E, and the found East 1/4 corner of Sec.1, T4N R37E. Since corner falls on a fractured basalt outcrop on a very steep West slope, a conventional monument is impractical. Instead, at the corner point determined by survey... Set a 5/8" x 22" iron pin driven into rock and surrounded with mortar. The 5/8" iron pin has a 1 1/2" aluminum cap, marked as shown in corner diagram.

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

No trees are within limits so I marked 2 bearing objects to reference the corner as follows: A 2'x1'x1' out of ground rock in place brs N49 1/2° W, 12.5' marked "XBO" on SE face. This rock in place is at the N edge of the same rock outcrop the corner is on. A 10"x10"x6" out of ground rock in place brs S48 1/2° W, 6.7' marked "XBO" on surface facing Northeast.

Painted bearing objects and rocks around corner red.

Set 6' steel fence post North of corner 24.7' to avoid the rock outcrop and attached sign 54-4.

Work Done By W.R.Wells Title Land Surveyor Date 9-01-88 State Registration No. or Agency ORLS 1106

Certified Cor. Record Prepared ? Yes No Filed At: County Surveyor Date _____

REMARKS

Index File No. E-25 T. 4 N. R. 37 E. WM. Tract or Surv. No. _____ Cor. _____