

OREGON CORNER RESTORATION FORM

Section: 15

Township: 4N

Range: 37 EWM

County: Umatilla

Date: 03/01/00

Corner Designation: K-14, N.W. 1/16 S. 15

Previous Renewals/Surveys, etc.: None

Monument(s) & Accessories Found (Condition & Source): None

Monument Detail: TOMKINS SURVEYING

N.W. 1/16

S. 15

T4N R37E

2000

PLS 2820

Monument Set (Procedures & Description): At surveyed position, set a 1 1/2" x 30" galvanized iron pipe with a 2 1/2" brass cap, marked as shown in Monument Detail. Erected a stone mound 4' in diameter 2' high around the monument.

New Accessories: A steel fence post with a land survey monument sign was placed 1' North of the corner.

An 18" Douglas fir bears N10°W, 40.2 feet. Scribed "NW 1/16 S15 BT".

A 20" Douglas fir bears N66°E, 77.0 feet. Scribed "NW 1/16 S15 BT".

A 16" Douglas fir bears S78°W, 66.2 feet. Scribed "NW 1/16 S15 BT".

A 24" Douglas fir bears S16°E, 90.8 feet. Scribed "NW 1/16 S15 BT".

All bearing trees have a 6" red band painted around them and a Umatilla County Bearing Object sign attached.

Location & Comments: The corner falls near top of North running ridge +/- 3500 feet South of the South fork of the Walla Walla River.

Compass Declination:

19° East

Firm/Agency: Tomkins Land Surveying, Inc.

20 E. Poplar, Suite 204

Walla Walla WA 99362

Party Chief: Joshua R. Martin

Notes: Joshua R. Martin

Witness: Ryan Lowery

Surveyor's Seal



RENEWS 12/31/01

12/15/00

RECEIVED BY

Umatilla County Surveyor

Date 12-00

Rec'd By SM

No. 00-258-C