

OREGON CORNER RESTORATION FORM

Section: 15

Township: 4 North

Range: 37 East, W.M.

County: Umatilla

Date: 06/22/2000

Corner Designation: K-17, North 1/16 corner on the East line of Section 15, applies to Section 15 only

Previous Renewals/Surveys, etc.: None

Monument(s) & Accessories Found (Condition & Source): None

Monument Detail: T4N R37E

N 1/16

S15 +

2000

LS 2820

Monument Set (Procedures & Description): At the position determined by survey, cemented a 2" brass disc in a drill hole at the base of a 12' high rock bluff,

New Accessories: Set 6' steel fence post 3' Northeast of the corner. A 16" Douglas fir bears N50°E 21.2 feet marked N1/16 S15 BT. A 15" Douglas fir bears S90°E 22.3 feet marked N 1/16 S15 BT. A 1" long "MAG" nail in a 1/2"x 1/2" drill hole 3" above the ground in a 3'x 3' rock face bears S12°E 2.6 feet. A 24" Douglas fir bears N69 1/2°W 64.4 feet marked N 1/16 S15 BT.

All bearing trees have a 6" wide red band painted around them and bearing object signs attached.

The bearing object is painted red and has a bearing object sign attached.

Location & Comments: This corner is located on a steep Northeasterly facing slope at the base of a 12' high rock bluff 800± South of the South Fork of the Walla Walla River.

Compass Declination:

19° East

Firm/Agency: Tomkins Land Surveying, Inc.

20 E. Poplar, Suite 204

Walla Walla WA 99362

Party Chief: Greg Flowers

Notes: Greg Flowers

Witness: Ryan Laughery

Surveyor's Seal

REGISTERED PROFESSIONAL LAND SURVEYOR

*Greg E. Flowers*

OREGON JUNE 30, 1997 GREG E. FLOWERS 02820LS

RENEWS 12/31/01

12/15/00

RECEIVED BY  
Umatilla County Surveyor  
Date 12-00  
Rec'd By SM  
No. 00-255-C