

OREGON CORNER RESTORATION FORM

Section: 15 & 22

Township: 4 North

Range: 37 East

County: Umatilla

Date: 06/22/2000

Corner Designation: N-15, 1/4 corner common to Sections 15 & 22.

Previous Renewals/Surveys, etc.: The corner was originally set by U.S. Deputy Surveyor, Geo S. Pershin, under contract No. 332, dated July 29, 1879. The Surveyor General's notes state: "set a basalt stone 24x10x6 on W. side of spur for 1/4 Sec. Cor. A pine, 24 ins., diam., brs. N48°W 165 lks. dist. A fir, 16 ins. diam. brs. S14°W, 11 lks. dist."

Monument(s) & Accessories Found (Condition & Source): Found the remains of a 48" pine stump, the Southerly 1/2 was completely burned away. No evidence of the fir bearing tree or the basalt stone was found. This area has been logged.

Monument Detail: T4N R37E

S15
1/4 +
S22
2000
LS 2820

Monument Set (Procedures & Description): S48°E 108.9 feet from the center of the pine stump, set a 1" x 30" galvanized iron pipe with a 2 1/2" brass cap, 6" in the ground to solid rock, surrounded with a mound of earth and stone 3 1/2 feet in diameter 2 feet high.

New Accessories: Set a 6 foot steel fence post with a survey monument sign attached in a mound of stone 3 feet North of the corner.

A rock outcropping 2 feet x 3 feet bears N20°E 16.2 feet marked "X" on the South face.

A 10" Douglas fir bears S26°E 59.4 feet, marked 1/4 S22 BT.

A 5" ponderosa pine bears S54°W 24.2 feet, marked 1/4 S22 BT.

A rock outcropping 3 feet x 3 feet bears N50°W 13.5 feet marked "X" on the Northwest face.

Bearing trees have a 6" red band painted around them with a bearing tree sign attached. Bearing objects are painted red and have bearing object signs attached.

Location & Comments: This corner is located on a steep Northwest facing spur ridge 200 feet ± North of an old logging road on the South side of the South Fork of the Walla Walla River.

Compass Declination:

19° East

Firm/Agency: Tomkins Land Surveying, Inc.

20 E. Poplar, Suite 204

Walla Walla WA 99362

Party Chief: Greg Flowers

Notes: Greg Flowers

Witness: Ryan Laughery

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Greg E. Flowers

OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/01

12/15/00

RECEIVED BY

Umatilla County Surveyor

Date 12-00

Rec'd By SIM

No. 00-254-C