

OREGON CORNER RESTORATION FORM

Section: 14 & 23

Township: 4 North

Range: 37 East

County: Umatilla

Date: 09/08/00

Corner Designation: N-19, 1/4 corner common to Sections 14 & 23

Renewals/Surveys, etc.: This corner was originally set by U.S. Deputy surveyors, Charles L. and William C. Campbell, under Contract No. 733, dated March 22, 1901. The Surveyor Generals notes state " set a basalt stone 15x12x6 ins. 10 ins. In the ground for 1/4 sec. cor. marked 1/4 on the W. face. From which a pine 28 ins. diam., bears S88°W 227 lks. dist. marked 1/4 S.23 BT, a pine 18 ins. diam., bears N65°30'W, 254 lks. dist., marked 1/4 S 14 BT.

Monument(s) & Accessories Found (Condition & Source): Found a 30" pine snag with visible scribes and a 30" ponderosa pine with healed blaze with an old bearing tree sign attached per the original survey by Campbell.

Monument Detail: T4N R37E

S14  
1/4 +  
S23  
2000  
PLS 2820

Monument Set (Procedures & Description): N88°E 149.8 feet from the center of the pine snag and S68E 161.7 feet from the center of the ponderosa pine bearing tree, set a 1"x 30" galvanized iron pipe with a 2 1/2" brass cap 8" in the ground surrounded with a mound of earth and stone

New Accessories: Set 6' steel fence post with a Umatilla County land survey monument sign N65°W 2 feet from the corner .

5/8" x 30" rebar reference monuments with a yellow plastic cap stamped "TOMKINS SURVEYING" attached were set 28" in the ground, a steel fence post with a Umatilla County Bearing Object sign attached were set alongside each R.M. The reference monuments (R.M.) bear from the corners as follows:

- N42°E 13.79 FEET
- S45°E 14.10 FEET
- S10 1/2°W 17.80 FEET
- N22°W 14.31 FEET

Location & Comments: This corner is located on a steep East facing hillside 3000'± South of the South Fork of the Walla Walla river.

Compass Declination:

19° East

Firm/Agency: Tomkins Land Surveying, Inc.  
20 E. Poplar, Suite 204  
Walla Walla WA 99362

Party Chief: Greg Flowers  
Notes: Greg Flowers  
Witness: Brianna Slater

Surveyor's Seal



RENEWS 12/31/01

12/15/00

RECEIVED BY

Umatilla County Surveyor

Date 12-00

Rec'd By SIM

Wn. 00-258-C