

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


E-1

History of original corner establishment:

Corner established by Robert F. Omeg, U.S. Deputy Surveyor, under his Contract No.761, dated June 16, 1905.

Surveyor General records state:

Set a basalt stone 15x8x6 ins. in a mound of stone for closing cor. for secs. 6 and 7, marked CC on E and 5 notches on S and 1 notch on N edge. And raised a mound of stone 2 ft base and 1 ft and a half high W of cor.



Description of corner evidence found:

No trace of original stone was found after a 2 1/2 hour search with a 2 person crew. The corner falls on a steep, unstable hillside.

The corner was reestablished on the East line of Section 12, T4N,R37E, (senior line), by single proportion measure between the East 1/4 corner of said Section 12, and the reestablished NE corner of said Section 12, using Robert Omeg's retracement measurements for proportioning.

Description of monument and accessories established to perpetuate the original location of this corner:

Since corner point falls on steep unstable hillside, (very rocky) and after spending about 45 minutes to dig 12" in depth, I conclude to remonument with a 5/8" x 30" iron pin. The iron pin was driven into a crack in the rocks and is very stable. Placed a 1 1/2" aluminum cap on the iron pin and marked it as shown in corner diagram. Set a 6' steel fence post South of corner and attached sign 54-4.

No bearing trees available for reference so I marked two bearing objects. A 10"x10"x12" out of ground rock in place brs S79°E, 54.8' marked "XBO" on NW face. A 12"x10"x10" out of ground rock in place brs N44°E, 7.2' marked "XBO" on SW face, painted bearing objects red.

Compass declination 19° East.

I hereby certify that the above described corner monument was properly reestablished by me on September 1, 1988.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of.....County Surveyor..... County of.....Umatilla.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the 17th day of October, 1988
David H. Kumbier by Kathleen Kumbier
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 10-88

Rec'd By [Signature]

No. 88-64-B

*GPO-591-971, 1988